



1. Remove existing wood shingles to bare wood. Existing roof deck is 1x4 batten with no underlayment. Replacement shingles to match existing shingles. New shingles are to be western red cedar #1 grade 18" long x random width and 1/4" thick at bottom edge. Shingles to be laid with 5" exposure or courses. Starter course to be a double thickness. Install new drip edge.
2. Clean all debris from site on a daily basis. Exposed roof shall be covered daily to prevent water infiltration to the building exterior.
3. Re-roofing the western section of the Mack House is an alternate.
4. Gutters were removed during recent house painting. Reinstallation of gutters is part of bid.

Contractor responsible to verify quantities
 BASE BID: 1550 SQUARE FEET
 ALTERNATE: 300 SQUARE FEET

PLAN

 CHANGES TO THE ORIGINAL

STEPHEN MACK HOUSE ROOF REPLACEMENT
 MACKTOWN FOREST PRESERVE
 2221 FREEPORT ROAD ROCKTON, ILLINOIS 61072

