



# WINNEBAGO COUNTY

— ILLINOIS —

---

County Administration Building  
404 Elm Street  
Rockford, Illinois 61101

Purchasing Department  
Phone: 815-319-4380  
Fax: 815-319-4381

March 5, 2025

## ADDENDUM ONE

### FLOORING REPLACEMENT FOR WINNEBAGO COUNTY ADULT PROBATION CENTER INVITATION FOR BID #25B-2392

All bid requirements and information have can be found at [www.wincoil.gov/purchasing](http://www.wincoil.gov/purchasing)

1. Will existing flooring be tested for asbestos? **Yes. We had samples taking February 24, 2025. We are awaiting results. Addendum Two will be posted with information from testing. Both Addendums will need to be acknowledged with Bid.**
2. **BID OPENING WILL BE MOVED TO MARCH 19, 2025 AT 10:00 AM.**
3. **Some flooring is two layers.**
  - i. 2nd floor public women's restroom 50 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
  - ii. 2nd floor public men's restroom 50 sq. ft. 1 layer of VCT
  - iii. 2nd floor staff women's restroom 72 sq. ft. 1 layer of VCT
  - iv. 2nd floor staff men's restroom 54 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
  - v. 2nd floor 3rd staff restroom 72 sq. ft. 1 layer VCT
  - vi. 2nd floor break area 168 sq. ft. 1 layer VCT
  - vii. 2nd floor elevator area 224 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
  - viii. 3rd floor public restroom 42 sq. ft. 2 layers of VCT
  - ix. 3rd floor staff women's restroom 80 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> ceramic
  - x. 3rd floor staff men's restroom 63 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> ceramic
  - xi. 3rd floor break area 168 sq. ft. Carpet
  - xii. 3rd floor elevator area 138 sq. ft. 2 layers of VCT
  - xiii. 4nd floor public women's restroom 50 sq. ft. 1 layer of VCT
  - xiv. 4nd floor public men's restroom 42 sq. ft. 1 layer of VCT
  - xv. 4nd floor drug test restroom 108 sq. ft. 1 layer of VCT
  - xvi. 4nd floor break area 60 sq. ft. 2 layers of VCT
  - xvii. 4th floor elevator area 112 sq. ft. This is carpet

4. What are the hours of operation for the Adult Probation Center? **Hours are from 8 AM to 7PM Monday – Friday.**
5. Can work be done after hours. **Yes. The 4<sup>th</sup> floor drug test restroom must be done after hours.**
6. Please clarify vinyl cove for project. **Please use 6-inch vinyl cove for inside all restrooms and 4-inch vinyl cove for breakrooms and in elevator/traffic areas.**
7. What color for the vinyl cove? **We will stay with the Charcoal 123 color that was listed in the solicitation.**
8. **Please include the Unisex bathroom on second floor in flooring price. This was not originally listed in solicitation.**
9. Do the toilets need to be pulled and reset? **Yes, please pull and reset after the flooring is installed.**
10. What should we do with ladies' patrician in restrooms? **We can work them at the time of flooring. They will need to be pulled and reset.**
11. Where is the staging for the install? **Vendors will have secure garage access, which will be scheduled with Ted Seele from facilities.**
12. Will there be a need for transition strips? **Yes.**

**END OF ADDENDUM ONE**

---