



# WINNEBAGO COUNTY

— ILLINOIS —

County Administration Building  
404 Elm Street  
Rockford, Illinois 61101

Purchasing Department  
Phone: 815-319-4380  
Fax: 815-319-4381

March 7, 2025

## ADDENDUM TWO

### FLOORING REPLACEMENT FOR WINNEBAGO COUNTY ADULT PROBATION CENTER INVITATION FOR BID #25B-2392

All bid requirements and information can be found at [www.wincoil.gov/purchasing](http://www.wincoil.gov/purchasing)

Will existing flooring be tested for asbestos? **Yes. We had samples taken February 24, 2025.**

**Below please see asbestos findings.**

Below you will find a list of the areas, the dimensions and what floor materials are currently in the spaces. The areas shaded in red contain asbestos material in the mastic. Winnebago County will have an abatement company remove all affected flooring in these rooms down to the concrete floor. It will be the responsibility of the awarded vendor/flooring company to floor these areas with requested flooring in the scope of work.

All areas not highlighted, the awarded vendor/flooring company will need to remove all existing flooring to the concrete floor and floor these areas with requested flooring in the scope of work.

- i. 2nd floor public women's restroom 50 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
- ii. 2nd floor public men's restroom 50 sq. ft. 1 layer of VCT
- iii. 2nd floor staff women's restroom 72 sq. ft. 1 layer of VCT
- iv. 2nd floor staff men's restroom 54 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
- v. 2nd floor 3rd staff restroom 72 sq. ft. 1-layer VCT
- vi. 2nd floor break area 168 sq. ft. 1-layer VCT
- vii. 2nd floor elevator area 224 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> layer is ceramic
- viii. 3rd floor public restroom 42 sq. ft. 2 layers of VCT
- ix. 3rd floor staff women's restroom 80 sq. ft. 2 layers of VCT
- x. 3rd floor staff men's restroom 63 sq. ft. 1<sup>st</sup> layer VCT 2<sup>nd</sup> ceramic
- xi. 3rd floor break area 168 sq. ft. Carpet
- xii. 3rd floor elevator area 138 sq. ft. 2 layers of VCT
- xiii. 4th floor public women's restroom 50 sq. ft. 1 layer of VCT
- xiv. 4th floor public men's restroom 42 sq. ft. 1 layer of VCT
- xv. 4th floor drug test restroom 108 sq. ft. 1 layer of VCT
- xvi. 4th floor break area 60 sq. ft. 2 layers of VCT
- xvii. 4th floor elevator area 112 sq. ft. This is carpet

Red highlight is asbestos containing material and will be abated before. Abated areas will have all flooring removed to concrete floor.

**END OF ADDENDUM TWO**