


1. Remove existing wood shingles to bare wood. Existing roof deck is 1x4 batten with no underlayment. Replacement shingles are to be western red cedar #2 grade or better 18" long x random width and 1/4" thick at bottom edge. Shingles to be laid with 5" exposure or courses. Starter course to be a double thickness. Install new drip edge.
2. Clean all debris from site on a daily basis. Exposed roof shall be covered daily to prevent water infiltration to the building exterior.
3. Re-roofing the western section of the Mack House is an alternate.
4. Gutters were removed during recent house painting. Reinstallation of gutters is part of bid.

PLAN

Contractor responsible to verify quantities

BASE BID: 1550 SQUARE FEET

ALTERNATE: 300 SQUARE FEET



STEPHEN MACK HOUSE ROOF REPLACEMENT MACKTOWN FOREST PRESERVE

2221 FREEPORT ROAD ROCKTON, ILLINOIS 61072

