



**TREE REMOVAL
4.5 ac**

**SILT FENCE (1200')
ALONG CREEK
DURING
CONSTRUCTION**

**NEW PRAIRIE
PLANTING
BY FOREST
PRESERVE**

**TREE REMOVAL
2 ac**

**POSSIBLE CONSTRUCTION
ENTRANCE**

SWANSON ROAD

**SOCCER
PLAYFIELDS**

BACKSTOP

**MODEL AIRPLANE
FLYING FIELD**

**BLACK WILLOW
SPRINGS
SHELTERHOUSE**

**REDCEDAR RIDGE
SHELTERHOUSE**

photo

NOTES

1. Contractor to call J.U.L.I.E. for a utility location prior to beginning work.
2. All vegetation to be flush cut at grade and treated with a 20%-30% tricopyr (e.g., Garlon 4E) and basal oil mixture as soon as possible after cutting. During the growing season a second application will be required prior to vegetation reaching a 3 foot height. Site conditions may require other chemicals be used to kill vegetation as described in specifications. In all chemical applications follow manufacturer's recommendations.
3. Cut and stack vegetation in burn piles. An alternate price is requested for all vegetation removed at Kieselburg to be disposed off-site

LEGEND

	LOOP TRAIL		SHELTER HOUSE
	CONNECTOR TRAIL		MODEL AIRPLANE FLYING FIELD
	PATH MARKER		OUTHOUSE
	PARKING		HAND PUMP
	PICNIC		INVASIVE SPECIES REMOVAL
	EVERGREEN		NEW PRAIRIE PLANTING
	LAWN		SILT FENCE

0 200 400 FEET

FIVE PRESERVE VEGETATION REMOVAL 12/13/2018
KIESELBURG FOREST PRESERVE
 5801 SWANSON ROAD ROSCOE, IL 61073