






**PHEASANTS FOREVER TO REMOVE INVASIVE UNDERSTORY (SHOWN IN BLUE)**

**NOTES**

1. Contractor to call J.U.L.I.E. for a utility location prior to beginning work.
2. All vegetation to be flush cut at grade and treated with a 20%-30% triclopyr (e.g., Garlon 4E) and basal oil mixture as soon as possible after cutting. During the growing season a second application will be required prior to vegetation reaching a 3 foot height. Site conditions may require other chemicals be used to kill vegetation. as described in specifications in all chemical applications follow manufacturer's recommendations.
3. All vegetation removed at Stone Bridge to be stacked into burn piles. Trees over 2" to be cut into 10 foot lengths. All burning by Forest Preserve.

	INVASIVE SPECIES REMOVAL (CONTRACT)
	INVASIVE SPECIES REMOVAL (VOLUNTEERS)
	SILT FENCE
 	

**PROJECT ACCESS IS FROM BELVIDERE ROAD**

FIVE PRESERVE VEGETATION REMOVAL  
**STONE BRIDGE FOREST PRESERVE**  
 6119 BUR OAK ROAD ROSCOE, IL 61073

12/13/2018