

## **ADDENDUM TWO**

Project No.: **RLJA PROJECT #: 22-053  
WC IFB #: 23B-2285**

Date: **May 4, 2023**

Subject: **CHANGES to the BIDDING DOCUMENTS**

Project: **REBID - HVAC REPLACEMENT PROJECT AT  
WINNEBAGO COUNTY JUVENILE DETENTION CENTER  
ROCKFORD, ILLINOIS**

Bids Due: **11:00AM, THURSDAY, MAY 11, 2023**


From: **ARCHITECT: RICHARD L. JOHNSON ASSOCIATES, INC.  
4703 CHARLES STREET  
ROCKFORD, IL 61108**

To: **ALL PROJECT DOCUMENT HOLDERS**

Please reproduce this Addendum as needed, and attach to the Project Manuals for the above project.

Bidders shall indicate receipt of this and all Addenda in the space provided on the Bid Form. Failure to do so may be sufficient cause to reject the bid.

Sincerely,  
RICHARD L. JOHNSON ASSOCIATES, INC.

  
\_\_\_\_\_  
Scott R. Johnson, AIA, LEED AP

This Addendum consists of:  
Pages 1 thru 2.  
Revised 30" x 42" Drawings E101 and E102  
Added 30" x 42" Drawings FP101

**NOTE:** Wherein this Addendum conflicts with the original Project Manual and Drawings, this Addendum shall govern.

## **CHANGES to the DRAWINGS**

### **1. DRAWING FP101**


1.1. Added sheet FP101 showing fire protection scope for the project.

### **2. DRAWINGS E101 & E102**

2.1. Added additional ceiling mounted devices required for removal (PXN) and reinstallation (PN) for new ceiling work.

**END ADDENDUM NUMBER 2**





**BASE BID  
DEMOLITION FLOOR PLAN - ELECTRICAL**

SCALE: 1/8" = 1'-0"

**GENERAL DEMOLITION NOTE**

- FOR ALL WALLS, CEILINGS, FLOORS, ETC. REQUIRED FOR CONSTRUCTION DEMOLITION WORK OR NEW CONSTRUCTION WORK, INCLUDING, BUT NOT LIMITED TO ITEMS SHOWN REMOVE (PX) AND/OR REMOVE AND RELOCATE (PXN-PN): ALL ELECTRICAL EQUIPMENT, DEVICES, BOXES, CONDUIT, WIRING, ETC., AS REQUIRED, FOR DEMOLITION OF PRESENT CONSTRUCTION AND TO AVOID INTERFERENCE WITH NEW CONSTRUCTION. (VERIFY EXISTING CONDITIONS FOR ALL REQUIRED WORK.)

**GENERAL DRAWING NOTES**

- CEILING MOUNTED DEVICES (FIRE ALARM, WIRELESS ACCESS POINT DEVICES, EXIT SIGNS, SPEAKERS, ANTENNAS, AND CAMERAS, ETC.) SHALL BE REMOVED (PXN) AS REQUIRED FOR CEILING DEMOLITION WORK. FIELD VERIFY EXISTING CONDITIONS FOR ALL REQUIRED WORK.
- LABEL PRESENT BREAKER AS "SPARE" WHERE PUMP HAS BEEN REMOVED (PX).

(P) FIRE ALARM CONTROL PANEL (NOTIFIER NFS-320)  
(P) PANEL "EH1" 400 AMP, 277/480V, 3PH, 4W SQUARE D I-LINE PANELBOARD  
(P) PANEL "DH1" 800 AMP, 277/480V, 3PH, 4W SQUARE D I-LINE PANELBOARD

(PX) HWP-2  
(PX) HWP-1

HVAC REPLACEMENT PROJECT AT  
 JUVENILE DETENTION CENTER FOR  
**WINNEBAGO COUNTY**  
 ROCKFORD, ILLINOIS

**RICHARD L. JOHNSON**  
 ASSOCIATES | ARCHITECTS

SHEET IDENTIFICATION  
**BASE BID  
ELECTRICAL DEMOLITION PLAN**

PROJECT INFORMATION	
Date	April 25, 2023
Rev. Date	May 4, 2023
Rev.	RLJA Proj
Rev.	2022-053R

SHEET NUMBER  
**E101**  
 OF  
 5

